

ADDENDUM NO. 4
TO THE CONTRACT DOCUMENTS
for
Wastewater System Improvements
Scott City, Missouri

The Contract Documents for Wastewater System Improvements in the City of Scott City are hereby changed as follows:

1. SECTION 6 – ELECTRICAL.

The following shall be added to Section 6 – ELECTRICAL in the Technical Specifications

15. Power Supply.

The contractor in addition to all wiring and conduit for the new equipment shall also replace the existing 400 amp manual transfer switch, 400 amp main disconnect, and 400 amp distribution panel with new electrical equipment rated at 600 amp. All wiring between the meter and distribution panel and genset and distribution panel shall be replaced as needed to handle the 600 amp load. New electrical equipment shall be provided to further distribute the power to the new wastewater equipment.

Richard Cochran, Jr., PE

February 10, 2026

*** End of Addendum No. 4 ***

